

## वसई विरार शहर महानगरपालिका

प्रभाग समिती आय  
ता. वसई, जि. पालघर

जावक क्र. वविशम/प्रसएफ/दिवा/ ३१६७ /२०१६-१७  
दि. २० / ०२ / २०१७

### जाहिर सुचना

वसई विरार शहर महानगरपालिका प्रभाग समिती आय मधील पाचुबंदर लिंगायत समाज दफनभूमी मध्ये विद्युतीकरण करून कायान्वित करणेचे आहे. तरी महापालिकेच्या अटी व शर्तीस अधिन राहून जाहिर सुचना प्रसिध्द करणेत येत आहे. सदर कामी सार्वजनिक बांधकाम विभागाकडील इच्छुक विद्युत परवाना धारक / नोंदणीकृत ठेकेदाराकडून कामाची दरपत्रके प्रसिध्दीच्या दिवसापासुन दिनांक- ०१ /०३ /२०१७ रोजी दुपारी २.०० वाजे पर्यंत प्रभाग समिती (आय) वसई कार्यालयात मागविण्यात येत आहे. ठेकेदारांनी खाली नमुद केलेल्या अंदाजपत्रकानुसार स्वतःच्या लेटर हेडवर कोटेशन सादर करावयाची आहेत. प्राप्त झालेली दरपत्रक शक्य झाल्यास त्याच दिवशी सायंकाळी ४.०० वाजता हजर ठेकेदार वा त्यांचे अधिकृत प्रतिनिधी यांच्या समोर प्रभारी सहा. आयुक्त यांच्या दालनात उघडण्यात येतील सदर कामी प्राप्त एक अथवा सर्व दरपत्रके कोणतेही कारण न देता नाकारण्याचा अधिकारी महानगरपालिकेने राखून ठेवला आहे. याची कारणे दिली जाणार नाहीत.

### ESTIMATE

#### PWD DSR 2015-16

NO	DESCRIPTION	DSR	UNIT	QTY	RATE	AMOUNT
1	Supplying & erecting ISI mark G.I.pole pole 'B' grade 75 mm. dia 6 mtr. long with pole cap, base plate in provided C.C. foundation and plinth.as per specification no . OH-PL / GIP	8-1-14/126	Nos	1.00	4611.76	4611.76
2	Supplying and erecting FRP box of size 300mm x 200mm x 125mm, 2.7mm thick complete on pole as per specification no. CB-SB.	7-8-8/119	Nos	1.00	652.36	652.36
3	Supplying and erecting modular type electronic step regulator two module ISI mark approved make duly erected on provided plate and box with wiring connections complete.	1-8-23/24	Nos	2.00	399.40	798.80
4	Point Wiring for light/bell/Exhaust fan in 20 mm. PVC conduit with 1.0 Sq.mm. FRLS grade copper wires with moduler type switch & required accesories as per specification NO: WG - PW/CW	1-9-6/28 & note no (6) pg 29	Nos	5.00	609.28	3046.40
5	Point Wiring for independent plug in 20 mm.rigid PVC conduit with 1.0 Sq.mm. FR grade copper wires with moduler type switch & socket & required accesories as per specification NO: WG - PW/CW	1-9-8/28 & note no (6) pg 29	Nos	1.00	727.28	727.28
6	Wiring for plug on board with switch socket with copper wiring & earthing & with moduler accesories as per specification NO: WG - PW/SW	1-9-13/28 & note no (6) pg 29	Nos	1.00	349.24	349.24
7	Supplying and erecting B grade G.I pipe/M.S pipe down rod duly painted for fan complete erected with PVC two core flexible cable 24/0.2 mm copper PVC wire.	2-12-6/58	Mtr	2.00	197.06	394.12

8	Supplying and erecting street light wall bracket made from 40 mm dia 'B' class GI pipe 1.2 mtr in total length complete as per specification no. FG-BKT/WB	2-6-4/51	Nos	6.00	592.66	3555.96
9	Supplying and erecting street light bracket for erection of single fitting made from 40 mm dia 'B' class GI pipe 1.0 mtr in length along with the pole cap of 300 mm. length 100 mm. dia duly welded as per specification no. FG-BKT/BPC	2-6-5/51	Nos	1.00	732.72	732.72
10	Supplying and erecting approved L.E.D.flood light of 50 Watt including lamp, having PF > 0.95, class IP 65 and above. Housing of pressure die cast aluminium alloy & heat sink extruded aluminium as per specification no. FG-ODF/FL	2-9-3/56	Nos	1.00	4457.00	4457.00
11	Supplying and erecting fan clamp of 30X5 mm. flat of required length & 10 mm. M.S bolt & nuts erected with necessary hook of 10 mm. M.S.round bar & painted	2-9-13/57	Nos	6.00	5182.00	31092.00
12	Supplying and erecting fan clamp of 30X5 mm. flat of required length & 10 mm. M.S bolt & nuts erected with necessary hook of 10 mm. M.S.round bar & painted	2-12-3/58	Nos	2.00	180.80	361.60
13	Supplying and erecting Ceiling fan of 1200 mm. sweep complete erected in position as per specification no FG-FN/CF	16-3-1/194	Nos	1.00	1340.86	1340.86
14	Supplying and erecting Ceiling fan of 1200 mm. sweep complete erected in position as per specification no FG-FN/CF	2-13-3/60	Nos	2.00	1802.26	3604.52
15	Providing and erecting 4 pole MCCB of 100 A. capacity with S.C rating of 35kA thermal and magnetic setting with provided leads on iron frame/laminated board as per specification no SW-SWR/MCCB	5-5-1/86 Note on Pg.86	Nos	9.00	6393.79	57544.11
16	Providing and erecting 4 pole MCCB of 200 A. capacity with S.C rating of 35kA thermal and magnetic setting with provided leads on iron frame/laminated board as per specification no SW-SWR/MCCB	5-5-3/86 Note on Pg.86	Nos	1.00	18501.99	18501.99
17	Supplying and erecting terminal spreaders for use on MCCB incoming & outgoing terminals for 4 poles upto 100 A. MCCB	5-11-6/94	Each	9.00	261.36	2352.24
18	Supplying and erecting terminal spreaders for use on MCCB incoming & outgoing terminals for 4 poles upto 250 A. MCCB	5-11-7/94	Each	1.00	1150.36	1150.36
19	Supplying and erecting extended rotary handle for MCCB with adjustable telescopic rod suitable for up to 100 A MCCB.	5-11-14/94	Each	9.00	1280.80	11527.20

20	Supplying and erecting extended rotary handle for MCCB with adjustable telescopic rod suitable for up to 100-250 A MCCB.	5-11-15/94	Each	1.00	1322.80	1322.80
21	G.I. sheet 1.6 mm (16 gauge ) to be used for fabrication of boxes panel boards including cutting, bending,drilling and welding rivetting etc.& painting with one coat of red oxide & two coats of enamel paint.	6-1-3/97	Sqm.	20.00	2102.86	42057.20
22	Supplying & erecting Iron work consisting of various sections of MS & including plates, chequered plates, Rods,Bars,MS pipes, etc. for panel board or other purpose with complete bending, cutting, drilling and welding complete erected at the position with neccessarymaterials duly painted with one coat of red oxide & two coats of enamel paint to match the switchgears or s per directions by the authority	6-1-19/98	Kg.	50.00	110.82	5541.00
23	Providing and erecting mounting type digital ammeter having three & half digit LED display external C.T. operated, calibrated for 0 to 1000A, AC suitable to operate on 500V AC supply with necessary PVC wire leads and lugs & mounting hardwareon provided panel complete with calibration certificate from manufacturer	6-3-11/101	Nos	1.00	2852.36	2852.36
24	Providing and erectingmounting type digital Volt meter having three & half digit LED display, calibrated for 0 to 750V, AC suitable to operate on 500V AC supply with necessary PVC wire leads and lugs & mounting hardwareon provided panel complete with calibration certificate from manufacturer	6-3-12/101	Nos	1.00	2599.36	2599.36
25	Providing and erecting Selector Switch suitable for voltmeter /Ammeter for 3 phase AC supply 500V, 50 Hz on provided box/panel and duly connected with necessary PVC wire leads and lugs	6-5-1/102	Nos	2.00	290.76	581.52
26	Providing & erectingL.T. Current Transformer with bar primary 50/5 to 1000/5 ratio with 15 Va burden erected in provided CRCA boxduly secured withinsulating materials connected to meter with test certificates	6-5-2/102	Nos	3.00	692.76	2078.28
27	Supplying and erecting LED type indicating pilot lamp with LED colours Red/Yellow/ Green, 230 / 250 V on provided box/panel with necessary material, wiring & connection etc	6-5-6/103	Each	2.00	751.76	1503.52

28	Supplying, Erecting & terminating PVC armoured cable 4 core 16 Sq mm. aluminium conductor with continuous 12.97 sqmm (8 SWG) GI Earth wire complete erected with glands & lugs on wall/ trusses/pole or laid in provided trench/ pipes as per specification no CB-LT/AL	7-1-16/108	Mtr	90.00	197.80	17802.00
29	Supplying and laying (including excavation) 50 mm. outside dia. Double wall corrugated pipes(DWC) of HDPE for enclosing cable below ground/road surface to required depth complete	7-6-11/117	Mtr	80.00	195.48	15638.40
30	Providing earthing with galvanised cast iron earth plate size 60x60x0.6 cm complete with all materials, testing and recording the result as per specification No EA-EP	9-1-1/139	Each	2.00	4117.12	8234.24
31	Supplying & Erecting copper stripe of required size used for earthing on wall & / or any other purpose with necessary copper clamps fixed on wall painted with bituminous paint in an approved manner with joints required.as specification no.EA-EP	9-2-2/140	Kg.	53.97	872.56	47092.06
32	Supplying and erecting pipe type earthing with 40 mm dia GI pipe or 20 mm dia Rod complete with all material as per specification no - EA-EP	9-1-4/139	Nos	2	1584.72	3169.44
33	Supplying and erecting mains with 2 x 1.0 sqmm FR copper PVC insulated wire laid in conduit / trunking / inside pole / busbar or any other places as per specification no : WG-MA/BW	1-3-1/13	Mtr	6	28.12	168.72
					Total Rs	297441.42
					Say Rs	297441.00

कामाचे दर

अ क्रं.	कामाचा तपशिल	दर
१	पाचुबंदर लिंगायत समाज दफनभूमी मध्ये विद्युतीकरण करणे.	अंदाजपत्रकिय दरावर अंकि-----% अक्षरी -----% कमी / जास्त दराने काम करण्यास तयार आहे.

कामाबाबतच्या अटी व शर्ती

१. अंदाजपत्रकिय दरावर टक्केवारी स्वरूपात दर मागविण्यात येत असून सार्वजनिक बांधकाम विभागाकडील मान्यता प्राप्त विद्युत परवाना धारक/नोंदणीकृत विद्युत ठेकेदारांकडून दरपत्रके मागविण्यांत येत आहेत. उशीराने आलेले, अर्धवट भरलेले, खाडाखोड करून स्वाक्षांकित न केलेले, सिलबंद न केलेले व सर्शत दरपत्रक फेटाळण्यात येतील. कोणतेही अथवा सर्व दरपत्रक कारण न देता नाकारणेचा हक्क महानगरपालिकेने राखून ठेवला आहे.

२. सदरचे काम उत्कृष्ट दर्जाचे साहित्य वापरून अंदाजपत्रकाप्रमाणे पूर्ण करून देणेस ठेकेदारावर बंधनकारक राहिल.

३. प्रत्यक्ष काम चालू असताना आजुबाजुच्या नागरिकाना, रहदरीचा त्रास, उपद्रव/ वा हानी होणार नाही याची जबाबदारी ठेकेदाराची असेल व तसेच अशा वेळी कोणाचीही आर्थिक /जिवितहानी झालेस त्याची नुकसान भरपाई ठेकेदारांना करून द्यावी लागेल याबाबत आवश्यक ते विमा संरक्षण घेणे ठेकेदारावर बंधनकारक राहिल.
४. सदरचे काम ठेकेदारास ३० दिवस मुदतीत पूर्ण करावे लागेल व कोणत्याही परिस्थितीत मुदतवाढ दिली जाणार नाही. तसेच अपवादात्मक परिस्थितीत मा. उपायुक्त यांचा निर्णय अंतीम राहिल
५. काम मुदतीत न झाल्यास प्रथम : प्रतिदिन रु १००/- एवढा दंड ठेकेदारांना अदा करावा लागेल व तसेच कामात प्रगती न आढळ्यास दंडाची रक्कम वाढविण्यात येईल.
६. ठेकेदारांना कामासाठी कार्यादेश दिलेनंतर त्वरीत कामाची सुरवात करावी लागेल व सदर कामात हयगय केल्यास सदरचा मक्ता रद्द करून त्याबाबत महानगरपालिकेचे आर्थिक नुकसान झाल्यास ते मुळ ठेकेदाराकडून वसूल करण्याचा अधिकार महापालिकेस राहिल.
७. मंजूर कोटेशन धारकाने एल.ई.डी.दिव्यांसाठी ३ वर्ष गॅरंटी द्यावयाची आहे. सदर कालावधीमध्ये दिवे बंद झाल्यास तात्काळ बदली करून
८. ठेकेदारांच्या देयकातून सुरक्षा अनामत व आयकराची प्रचलित दरानुसारची रक्कम कपात करून उर्वरित रक्कम अदा केली जाईल तसेच सुरक्षा अनामतीची रक्कम सुरक्षा कालावधीत (६ महिने) यशस्वीरित्या पूर्ण झाले नंतर अदा केले जाईल.
९. प्रत्यक्ष काम चालू असताना कामाच्या प्रकारात बाबींच्या परिणामात चढ/ उतार / घट / वाढ झाल्यास त्याप्रमाणे कार्यवाही ठेकेदारास करावी लागेल.
१०. कामाचे देयक अदा केले नंतर भविष्यात सदर कामी महानगरपालिकेच्या लेखा परिक्षणात आक्षेप आल्यास फरकाची/ वा आक्षेपा
११. महापालिकेकडे उपलब्ध तरतुद व निधी नुसार सदर कामाचे देयक अदा करण्यात येईल.
१२. काम भारतीय विज अधिनियम १९५६ (सुधारीत) नुसार करणे विद्युत ठेकेदारावर बंधनकारक राहिल.

उपायुक्त तथा नियंत्रण अधिकारी  
प्रभाग समिती आय  
वसई विरार शहर महानगरपालिका